Primary Containment Vessel of Unit 2 of Fukushima Daiichi Nuclear Power Station Sampling Result of the Gas Control System

March 1, 2012 Tokyo Electric Power Company

[Sampling place] Inlet of the gas control system in PCV of Unit 2

【Sampling time and date 】10:54 am, February 29, 2012 (Wed)

[Result]

Nuclides		Density of radioactive materials (Bq/cm³)	Detection limits (Bq/cm³)	Half-life
Gas vial container	I-131	Below detection limit	1.2 × 10 ⁻¹	About 8 days
	Cs-134	4.7 × 10 ⁻¹	3.0×10^{-1}	About 2 years
	Cs-137	6.2 × 10 ⁻¹	3.7×10^{-1}	About 30 years
	Kr-85	Below detection limit	2.9×10^{1}	About 11 years
	Xe-131m	Below detection limit	$3.0 \times 10^{\circ}$	About 12 days
	Xe-133	Below detection limit	2.3 × 10 ⁻¹	About 5 days
	Xe-135	Below detection limit	1.0 × 10 ⁻¹	About 9 hours

Each of short half-life Xe was below detection limit.

[Reference] In regard to judgment of subcriticality of Unit 1, we confirmed that the density of Xe-135 radioactivity did not exceed the criteria of recriticality, which is 1Bq/cm³, using the radiation dose detector placed in the gas management system. (February 29 measured value of Xe-135 : (1.7 ~ 2.8) x 10⁻³Bq/cm³)

^{*} Below the criterion to judge criticality, 1 Bq/cm³ (Xe-135)